



# Timișoara North Water Supply & Sewerage Systems

## Data and facts

<b>Company</b>	PORR Construct S.R.L. (55%) in JV with Saif-Tim SA, Tuboterm Construct SRL, Formin SA
<b>Type</b>	Pipeline construction
<b>Runtime</b>	11.2012 - 01.2016
<b>Principal</b>	AQUATIM S.A.

[Project report online](#)

[www.porr-group.com](http://www.porr-group.com)



# New pipes for Timișoara

The scope of work for the sewerage system included not only the installation of 150mm to 1,000mm long GRP pipes on a stretch of 13km, but also the construction of 290 manholes and about 530 household connections.

For the water supply system, PORR also executed the installation of around 9.5km of pipes, thereof 6.8km of HDPE pipes with diameters of up to 355mm and 0.65km DI pipes with diameters of up to 400mm. Furthermore, the work on the water supply system comprised around 225 household connections as well as the construction of 40 large valve chambers.

Most of the pipelaying was executed in an open trench. However, about 190m of sewer pipes and 2,000m of water pipes had to be installed trenchless and were executed through horizontal drilling. The project was successfully completed in January 2016.

## Impressions



## Image notes

1

Rehabilitation and extension.

Most of the installation activities were executed in an open trench.

2

New sewerage and water supply system.

The rehabilitation and extension was executed by PORR together with other construction companies.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

**PORR AG Group Communications**

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: [comms@porr-group.com](mailto:comms@porr-group.com)